ES26-086 Villa Bosnia - External finishes take-off (Dryvit direct-applied over Nudura ICF)	m2
Gross external ICF wall face (true faces, ground to parapet top)	583.7
less external openings	-143.7
NET facade	440
of which stone-look textured (tan)	343.3
of which grey smooth render panels	43.5
of which timber-look slat zones (background render; slats by others)	30.6
of which dark plinth band (300 mm)	22.5
Reveals (heads + jambs, 150 mm)	29.9
Parapet inner faces	67.1
Parapet tops (under coping by others)	39.7
TOTAL Dryvit base coat + mesh area	576.7
illbruck ME110 internal window membrane (m, net)	205.2

Elevation	Sheet	Gross m2	Openings m2	Net m2	Stone-look	Grey render	Slat zone	Plinth	Reveals	No. openings
Front - facade 1-9	20	146.8	40.3	106.5	81.6	5.3	15	4.6	9.1	9
Side - facade A-H	21	141.5	47.3	94.2	60.6	22.7	5.2	5.8	8	7
Rear - facade 9-1	22	152.9	22.8	130.2	111.9	7.1	5.1	6	4.9	5
Side - facade H-A	23	142.4	33.3	109.1	89.1	8.4	5.4	6.1	7.9	8
TOTAL		583.7	143.7	440	343.3	43.5	30.6	22.5	29.9	29

Opening	Tag	Level	Type	Elevation	W m	H m	Area m2	ME110 m (perimeter)	Reveal m
L1-W1-3	W 1-3	L1	window	Side - facade H-A	1.1	2.645	2.91	6.39	6.39
L1-GD-1	GD-1	L1	door	Front - facade 1-9	5.7	2.645	15.077	10.99	10.99
L1-W1-2	W 1-2	L1	window	Side - facade A-H	1.1	2.645	2.91	6.39	6.39
L1-W1-5	W 1-5	L1	window	Side - facade H-A	1.1	2.25	2.475	5.6	5.6
L1-W1-4	W 1-4	L1	window	Side - facade H-A	1.1	2.25	2.475	5.6	5.6
L1-W1-6	W 1-6	L1	window	Side - facade H-A	1.51	3.2	4.832	7.91	7.91
L1-W1-7	W 1-7	L1	window	Side - facade H-A	3	2.7432	8.23	8.486	8.486
L1-W1-8	W 1-8	L1	window	Rear - facade 9-1	1	2.7432	2.743	6.486	6.486
L1-W1-11	W 1-11	L1	window	Side - facade A-H	1	2.2004	2.2	6.401	5.401
L1-W1-10	W 1-10	L1	window	Side - facade A-H	1.5	2.2004	3.301	7.401	5.901
L1-W1-12	W 1-12	L1	window	Side - facade A-H	3.9	2.7432	10.698	9.386	9.386
L1-W1-13	W 1-13	L1	window	Rear - facade 9-1	3.25	2.7432	8.915	8.736	8.736
L1-W1-14	W 1-14	L1	window	Side - facade A-H	3.84	2.7432	10.534	9.326	9.326
L1-W1-16	W 1-16	L1	window	Front - facade 1-9	1	2.7432	2.743	6.486	6.486
L1-W1-15	W 1-15	L1	window	Front - facade 1-9	1	2.7432	2.743	6.486	6.486
L1-W1-1	W 1-1	L1	window	Front - facade 1-9	1.2	2.7432	3.292	6.686	6.686
L1-W1-9	W 1-9	L1	window	Side - facade H-A	1	2.2004	2.2	6.401	5.401
L2-W1-6-upper	W 1-6	L2	window	Side - facade H-A	1.51	2.185	3.299	7.39	5.88
L2-W2-4	W 2-4	L2	window	Side - facade H-A	3	2.285	6.855	7.57	7.57
L2-W2-5	W 2-5	L2	window	Rear - facade 9-1	1	2.285	2.285	5.57	5.57
L2-W2-6	W 2-6	L2	window	Rear - facade 9-1	1	1.39	1.39	4.78	3.78
L2-W2-7	W 2-7	L2	window	Side - facade A-H	3.9	2.285	8.912	8.47	8.47
L2-W2-8	W 2-8	L2	window	Rear - facade 9-1	3.25	2.285	7.426	7.82	7.82
L2-W2-9	W 2-9	L2	window	Side - facade A-H	3.84	2.285	8.774	8.41	8.41
L2-W2-10	W 2-10	L2	window	Front - facade 1-9	1	2.285	2.285	5.57	5.57
L2-W2-11	W 2-11	L2	window	Front - facade 1-9	1	2.285	2.285	5.57	5.57
L2-W2-1	W 2-1	L2	window	Front - facade 1-9	1.2	2.285	2.742	5.77	5.77
L2-W2-2	W 2-2	L2	window	Front - facade 1-9	3	2.285	6.855	7.57	7.57

L2-W2-3	W 2-3	L2	window	Front - facade 1-9	1	2.285	2.285		5.57	5.57
TOTAL							143.67		205.22	199.21

Layer	Product (Tremco CPG / Dryvit)	Unit	Qty	Basis
Base coat	Dryvit Primus M / Genesis base coat 25 kg	pail	53	all rendered m2, 130 ft2/pail, +10%
Mesh	Dryvit Standard Plus mesh 4.3 oz (laps incl.)	m2	663.2	+5% laps +10% waste
Mesh	Dryvit Panzer / intermediate mesh - plinth impact zone	m2	24.8	plinth band
Mesh	Diagonal mesh patches 300 x 200 at opening corners	nr	68	head corners + sill corners
Primer	Dryvit Color Prime 4 gal - tinted to each finish	pail	23	300 ft2/pail
Finish - stone-look	Dryvit Lymestone / Stone-look textured finish (tan)	m2	377.6	body of every facade
Finish - grey render	Dryvit Sandpebble Fine, grey (smooth band panels)	m2	47.9	grey panels above/between glazing
Finish - slat zone	Dryvit Sandpebble Fine, dark (background behind timber-look slats)	m2	33.7	slats themselves = by others (RFI)
Finish - plinth	Dryvit Stone Mist / dark granite-look finish	m2	24.8	300 mm band at wall base
Finish - reveals + parapets	Finish to match adjoining facade	m2	150.3	reveals, parapet inner faces, parapet tops
Below-ground / DPC	Dryvit AquaFlash / Backstop NT waterproof coating to the plinth below DPC	m2	24.8	where the wall meets ground
Beads	Starter track / base drip bead	m	110.2	wall base perimeter
Beads	PVC corner bead with mesh	m	199.5	external corners + opening jamb arrises
Beads	Reveal / window return bead	m	209.2	heads + jambs
Sealant	Tremco Dymonic 100 - frame perimeters (ext)	m	215.5	every external opening
Tapes	illbruck ME110 Interior Window Membrane 100 mm (25 m roll)	roll	10	205.2 m net, +10% = 225.7 m - INTERNAL ONLY

Assumptions / RFIs

System: Dryvit direct-applied over the Nudura EPS (no added insulation board) - confirm system + any added CI with Tremco CPG Poland.
Finish split measured from the rendered elevations (sheets 20-23) by colour class and applied to the true wall faces per elevation.
Timber-look slats are a cladding product (by others) - rendered background quantified behind them. RFI: slat product + fixings into the ICF.
Plinth = 300 mm dark band at every wall base; waterproof coating below DPC. Below-ground walls are not finished (garage front ICF base -700).
Parapet inner face taken as 660 mm at 2F and 450 mm on single-storey parts; copings by others.
Reveals 150 mm at heads + jambs; sills = cills by others. Windows set to the inside face (ME110 internal membrane only, standing rule).
Outdoor kitchen columns, pool walls and terrace upstands are not ICF and not included.
Garage door GD-1 counted as an opening; its ME110 perimeter is included for the frame seal - remove it if the door supplier seals the sectional door frame.
Finish areas are the modelled ICF faces: masonry above the garage ICF (+2.400 to the drawn garage parapet) is not included.